

FMFOOT - MINIFOOT

Description:
Minifoot for mounting support



FMFOOT

OTHER ADDITIONAL INFORMATION

Summary of TUV Test Report

Incoming Release Note	Not Formally Released
Date of Receipt	9 September 2016
Test Items	Twin Minifoot with 250mm Channel Minifoot 110mm Minifoot 160mm with base
Number of Items tested	3
Model/Part Numbers	N/A
Serial Numbers	N/A
Test Plan/Issue/Date	Customer Defined
Test Specification/Date	Customer Defined
Deviations from the Standard	None
Date of Test	9 September 2016

Test Descriptions

Test 1: Twin Minifoot with 250mm Channel: 100kg load applied (2 x SWL) to sample for 30 minutes duration. Upon completion of the aforementioned test a 1,350kg load was applied.
 Test 2: Minifoot 110mm: 50kg (2 x SWL) load applied to sample for 30 minutes duration. Upon completion of the aforementioned test a 1,350kg load was applied.
 Test 3: Minifoot 160mm with base: 100kg (2 x SWL) load applied to sample for 20 minutes duration. Upon completion of the aforementioned test a 1,350kg load was applied.

Results of Test

Test 1: The Twin Minifoot with 250mm Channel sample showed no signs of damage after the 100kg and 1,350kg load tests.
 Test 2: The minifoot 110mm sample showed no signs of damage after the 50kg and 1,350kg load tests.
 Test 3: The minifoot 160mm with base sample showed no signs of damage after the 100kg and 1,350kg load tests.

This Certificate relates only to the actual item tested.

The tests above were applied to the test samples as a vertical compressive load using an MTS 842 Compression Machine.100kg